

THE NETHERLANDS
(N E D E R L A N D)

COMMUNICATION

Concerning ⁽¹⁾:

- ~~approval granted~~
- ~~approval extended~~
- ~~approval refused~~
- ~~approval withdrawn~~
- ~~production definitively discontinued~~

of a type of CNG/LNG component pursuant to Regulation number 110.



Approval number: E4*110R05/00*0369*02

1. CNG/LNG component considered:

- ~~Container(s) or cylinder(s)~~⁽⁺⁾
- ~~Tank(s) or vessel(s)~~⁽⁺⁾
- ~~CNG accumulator(s)~~⁽⁺⁾
- ~~Pressure indicator~~⁽⁺⁾
- ~~Pressure relief valve~~⁽⁺⁾
- ~~Automatic valve(s)~~⁽⁺⁾
- ~~Excess flow valve~~⁽⁺⁾
- ~~Gas tight housing~~⁽⁺⁾
- ~~Pressure regulator(s)~~⁽⁺⁾
- ~~Non return valve(s) or check valve(s)~~⁽⁺⁾
- ~~Pressure relief device (PRD)(temperature triggered)~~⁽⁺⁾
- ~~Manual valve~~⁽⁺⁾
- ~~Flexible fuel lines~~⁽⁺⁾
- ~~Filling unit or receptacle~~⁽⁺⁾
- ~~Gas injector(s)~~⁽⁺⁾
- ~~CNG Compressor~~⁽⁺⁾
- ~~Gas flow adjuster~~⁽⁺⁾
- ~~Gas/air mixer~~⁽⁺⁾
- ~~Electronic control unit~~⁽⁺⁾
- ~~Pressure and temperature sensor(s)~~⁽⁺⁾
- ~~CNG filter(s)~~⁽⁺⁾
- ~~PRD (pressure triggered)~~⁽⁺⁾
- ~~Fuel rail~~⁽⁺⁾
- ~~Heat exchanger(s)/vaporizer(s)~~⁽⁺⁾
- ~~Natural gas detector(s)~~⁽⁺⁾



- ~~LNG filling receptacle(s)⁽⁺⁾~~
- ~~LNG pressure control regulator(s)⁽⁺⁾~~
- ~~LNG pressure and/or temperature sensor(s)⁽⁺⁾~~
- ~~LNG manual valve(s)⁽⁺⁾~~
- ~~LNG automatic valve(s)⁽⁺⁾~~
- ~~LNG non return valve(s)⁽⁺⁾~~
- LNG pressure relief valve(s)⁽¹⁾
- ~~LNG excess flow valve(s)⁽⁺⁾~~
- ~~LNG fuel pump(s)⁽⁺⁾~~
-

2. Trade name or mark : LNG Pressure Relief Valve NG900x series
3. Manufacturer's name and address : Engineered Controls International LLC
100 RegO Drive 27244
Elon, North Carolina
United States of America
4. If applicable, name and address of manufacturer's representative : N.A.
5. Submitted for approval on : 04-08-2014
6. Technical service responsible for conducting approval tests : Kiwa Nederland B.V.
P.O. Box 137
7300 AC Apeldoorn
The Netherlands
7. Date of report issued by that service : 31-01-2023
8. Number of report issued by that service : 127072_P000277086
9. Approval : ~~granted/refused/extended/withdrawn~~⁽¹⁾
10. Reason(s) of extension (if applicable) : The current homologated LNG Pressure Relief valve NG900x series are extended with the new NG9002TX Type
- The currently homologated LNG Pressure Relief Valve NG900x series is updated to the latest Revision of the ECE Regulation 110
11. Place : Zoetermeer
12. Date : 13 February 2023
13. Signature : 

14. The documents filed with the application or extension of approval can be obtained upon request.

⁽¹⁾ Strike out what does not apply.

ADDENDUM

1. Additional information concerning the type approval of a type of ~~CNG~~/LNG components pursuant to Regulation number 110.
 - 1.1. Natural Gas Storage System
 - 1.1.1. Container(s) or cylinder(s) (for CNG system)
 - 1.1.1.1. Dimensions :
 - 1.1.1.2. Material :
 - 1.1.2. Tank(s) or vessel(s) (for LNG system)
 - 1.1.2.1. Capacity :
 - 1.1.2.2. Material :
 - 1.1.3. CNG accumulator
 - 1.1.3.1. Dimensions :
 - 1.1.3.2. Material :
 - 1.1.3.3. Capacity :
 - 1.2. Pressure indicator
 - 1.2.1. Working pressure(s) ⁽²⁾ :
 - 1.2.2. Material :
 - 1.3. Pressure relief valve (discharge valve)
 - 1.3.1. Working pressure(s) ⁽²⁾ :
 - 1.3.2. Material :
 - 1.4. Automatic valve(s)
 - 1.4.1. Working pressure(s) ⁽²⁾ :
 - 1.4.2. Material :
 - 1.5. Excess flow valve
 - 1.5.1. Working pressure(s) ⁽²⁾ :
 - 1.5.2. Material :
 - 1.6. Gas-tight housing
 - 1.6.1. Working pressure(s) ⁽²⁾ :
 - 1.6.2. Material :
 - 1.7. Pressure regulator(s)
 - 1.7.1. Working pressure(s) ⁽²⁾ :
 - 1.7.2. Material :
 - 1.8. Non-return valve(s) or check valve(s)
 - 1.8.1. Working pressure(s) ⁽²⁾ :
 - 1.8.2. Material :
 - 1.9. Pressure relief device (temperature triggered)
 - 1.9.1. Working pressure(s) ⁽²⁾ :
 - 1.9.2. Material :
 - 1.10. Manual valve
 - 1.10.1. Working pressure(s) ⁽²⁾ :
 - 1.10.2. Material :




1.11.	Flexible fuel lines	
1.11.1.	Working pressure(s) ⁽²⁾	:
1.11.2.	Material	:
1.12.	Filling unit or receptacle	
1.12.1.	Working pressure(s) ⁽²⁾	:
1.12.2.	Material	:
1.13.	Gas injector(s)	
1.13.1.	Working pressure(s) ⁽²⁾	:
1.13.2.	Material	:
1.14.	Gas flow adjuster	
1.14.1.	Working pressure(s) ⁽²⁾	:
1.14.2.	Material	:
1.15.	Gas/air mixer	
1.15.1.	Working pressure(s) ⁽²⁾	:
1.15.2.	Material	:
1.16.	Electronic control unit	
1.16.1.	Basic software principles	:
1.17.	Pressure and temperature sensor(s)	
1.17.1.	Working pressure(s) ⁽²⁾	:
1.17.2.	Material	:
1.18.	CNG filter(s)	
1.18.1.	Working pressure(s) ⁽²⁾	:
1.18.2.	Material	:
1.19.	PRD (pressure triggered)	
1.19.1.	Working pressure(s) ⁽²⁾	:
1.19.2.	Material	:
1.20.	Fuel rail(s)	
1.20.1.	Working pressure(s) ⁽²⁾	:
1.20.2.	Material	:
1.21.	Heat Exchanger(s)/Vaporizer(s)	
1.21.1.	Working pressure(s) ⁽²⁾	:
1.21.2.	Material	:
1.22.	Natural gas detector(s)	
1.22.1.	Working pressure(s) ⁽²⁾	:
1.22.2.	Material	:
1.23.	LNG filling receptacle(s)	
1.23.1.	Working pressure(s) ⁽²⁾	:
1.23.2.	Material	:
1.24.	LNG pressure control regulator(s)	
1.24.1.	Working pressure(s) ⁽²⁾	:
1.24.2.	Material	:



1.25.	LNG pressure and/or temperature sensor(s)	
1.25.1.	Working pressure(s) ⁽²⁾	:
1.25.2.	Material	:
1.26.	LNG manual valve(s)	
1.26.1.	Working pressure(s) ⁽²⁾	:
1.26.2.	Material	:
1.27.	LNG automatic valve(s)	
1.27.1.	Working pressure(s) ⁽²⁾	:
1.27.2.	Material	:
1.28.	LNG non-return valve(s)	
1.28.1.	Working pressure(s) ⁽²⁾	:
1.28.2.	Material	:
1.29.	LNG pressure relief valve(s)	
1.29.1.	Working pressure(s) ⁽²⁾	: 151 kPa up to 2860 kPa
1.29.2.	Material	: See report 127072 and its extensions
1.30.	LNG excess flow valve(s)	
1.30.1.	Working pressure(s) ⁽²⁾	:
1.30.2.	Material	:
1.31.	LNG fuel pump(s)	
1.31.1.	Working pressure(s) ⁽²⁾	:
1.31.2.	Material	:
1.32.	CNG Compressor	
1.32.1.	Working pressure(s) ⁽²⁾	:
1.32.2.	Material	:

⁽²⁾ Specify the tolerance



Report 127072_P000277086
31-01-2023

Test report

LNG Pressure Relief Valve NG900x series



Applicant

Engineered Controls International, LLC
100 RegO Drive 27244
Elon, North Carolina
United States of America

**Trust
Quality
Progress**

Contents

1	Summary of testing.....	5
2	Description of the product.....	6
3	Report history	7
4	Measurement uncertainty	8
5	Appendices	9
6	End of report	14

© 2023, Kiwa Nederland B.V.

This report may only be duplicated as a complete set without any modifications and with permission of the legitimate owner. The test results in this report are exclusively related to the samples offered and tested.

Tests marked in this report with the IRN number are part of the accreditation scope (RvA L248) unless stated differently. Measurement uncertainty of testing in the context of ISO/IEC 17025.

Test reports can, in some cases, contain besides the numeric measured values also the qualification "pass" or "fail". In this assessment, compliance with the specification limit from the applicable product standard is used. The measurement complies with the requirement if the probability of its being within the limit is at least 50%.

This does not take into account the measurement uncertainty associated with the test method.

It is explicitly stated that in the case of a "pass" or "fail", the measured result is corrected for the measurement uncertainty and/or the relevant test conditions for the measured result.

Unless otherwise noted the measurement uncertainty and conditions are as specified in the test specifications.

This report is only valid when signed by the test person and reviewer.

- RDW designation number for E4 and e4: RDWT-CAC-04
- KBA designation number for E1 and e1: KBA-P00033-12

Conclusions for compliance with e.g. product standard requirements are not part of the lab scope (RvA L248).


In case when information is supplied by the customer it is possible that it can affect the validity of results.

In case of dispute regarding this test report please contact Kiwa Nederland B.V.

Version: 004

TEST REPORT
LNG Pressure Relief Valve NG900x series

In accordance with ECE R110

Report number	:	127072	
Job reference	:	P000277086	
Date of issue	:	31-01-2023	
Total number of pages	:	14 (including appendices)	
Testing laboratory	:	KIWA Nederland B.V.	
Testing location/address	:	Wilmersdorf 50 7327 AC Apeldoorn The Netherlands	
Applicant's name	:	Engineered Controls International, LLC	
Address	:	100 RegO Drive 27244 Elon, North Carolina United States of America	
Manufacturers location	:	Engineered Controls International, LLC	
Address	:	100 RegO Drive 27244 Elon, North Carolina United States of America	
Scope	:	Testing of LNG Pressure Relief Valve regarding the requirements as derived from the below mentioned Test specifications.	
Test specifications	:		
Standards	:	Regulation 110 Addendum 109: Regulation No. 110 Revision 6 - Amendment 4 05 series of amendments– Date of entry into force: 22 June 2022	
Non-standard test method	:	N.A.	
Component description	:	LNG Pressure Relief Valve NG900x series	
Manufacturer	:	Engineered Controls International, LLC	
Trade Mark	:	RegO Products	
Model/Type reference	:	LNG Pressure Relief Valve NG900x series (a full overview can be found in chapter 2: Description of the product)	

Sample number(s) : N.A.
Intake date sample(s) : N.A.
Date(s) of testing : N.A.

Remarks : N.A.

Summary : Complies with the requirements as far as identified in the attached test- and result sheets.

Tested by : Eric Harmsen
(name + signature)

A handwritten signature in black ink, appearing to read "Eric Harmsen", written over a light blue horizontal line.

Reviewed by : Regina Adelmann
(name + signature)

A handwritten signature in purple ink, appearing to read "Regina Adelmann", written over a light blue horizontal line.

1 Summary of testing

On request of Engineered Controls International, LLC the items as mentioned under Test item description are tested according to the Test specifications (see page 3 of this report).

Based on the product(s) information the test plan is not subject to any special interpretations or modifications.

The following modifications are made to the LNG Pressure Relief Valve NG900x series

- The current homologated LNG Pressure Relief valve NG900x are extended with the new NG9002TX Series
- The currently homologated LNG Pressure relief valve NG900x series is updated to the latest Revision of the ECE Regulation 110

As a result, no tests are carried out

Notes

- The described test results are only valid for the tested materials and objects.
- RDW designation number for E4 and e4: RDWT-CAC-04
- KBA designation number for E1 and e1: KBA-P00033-12

2 Description of the product

The information below is based on the test results on the models under testing and the information of the manufacturer.

LNG Pressure Relief Valve NG900x series

Approval number(s)	:	E4*110R05/00*0369*02
Marking number(s)	:	E4-110R-050369 "L"
Manufacturer	:	Engineered Controls International, LLC
Brand name(s)	:	RegO Products Macro Technologies LLC
Type(s) :		Angle relief valve: NG9008MA200 up to NG9008MA460 NG9002T SER NG9002T015 up to NG9002T0459 NG9002TX SER NG9002TXA up to NG9002TXK
Working pressure	:	151 kPa up to 2860 kPa
Classification	:	Class 5
Temperature range	:	-162°C up to 85°C
Material(s)	:	see drawings

3 Report history

Report number : **127072**
Project number : **127072**
Approval number : E4-110R-010369 "L"
Report date : 04-08-2014
Author : Eric Harmsen
Description : Initial report
LNG Pressure Relief Valve NG900x series

Report number : **127075**
Project number : **180101491**
Approval number : E4*110R02/00*0369*01
Marking number : E4-110R-020369 "L"
Report date : 02-02-2018
Author : Henry Rooks
Description : Extension 01

The following modifications are included:

Addition of the NG9002T series relief valve to the already homologated NG9008M Series. The manually opening handle is omitted from the NG9008M Series relief valve. The new developed type NG9002T Series relief valve is made from the same material as the already homologated type and there are no further design changes.

Referring to the latest Supplement version of the ECE Regulation 110 the E4 marking number for the LNG Pressure relief valve NG900x series has been changed to E4-110R-020369-L.

According to Agreement 1958 Rev.3 the certificate number is updated to: E4*110R02/00*0369*01

Report number : **127072**
Project number : **P000277086**
Approval number : E4*110R05/00*0369*02
Marking number : E4-110R-050369 "L"
Report date : 31-01-2023
Author : Eric Harmsen
Description : Extension 02

The following modifications are included:

The current homologated LNG Pressure Relief valve NG900x are extended with the new NG9002TX Series

The currently homologated LNG Pressure Relief valve NG900x series is updated to the latest Revision of the ECE Regulation 110.

4 Measurement uncertainty

Measurement uncertainty of testing in the context of ISO/IEC 17025

Applied equipment

The applied equipment in the department Automotive are in the calibration database ICS2000, in this database the equipment of the department is stated with the applicable measurement uncertainty. This database is controlled by the calibration department.

Applied measurement uncertainty

In the laboratory the OM 3.10.7 applies.

Unless otherwise specified in the test specifications the measurement uncertainty and conditions applied are:

Voltage	$\pm 2 \% \text{ Reading}$
High voltage test device (SPS) 500 – 3750 Vac	$\pm 5 \% \text{ Reading}$
Resistance	$\pm 2 \% \text{ Reading}$
Protective wire and insulation test device	$\pm 5 \% \text{ Reading}$
Sliding gauge	$\pm 0.1 \text{ mm}$
Measuring tape	$\pm 1 \text{ mm}$
Cooling and heating $< -10 \text{ }^{\circ}\text{C}$	$\pm 5 \text{ }^{\circ}\text{C}$
Cooling and heating $-10 \text{ }^{\circ}\text{C} / +100 \text{ }^{\circ}\text{C}$	$\pm 3 \text{ }^{\circ}\text{C}$
Cooling and heating $> 100 \text{ }^{\circ}\text{C}$	$\pm 5 \% \text{ Reading}$
Climate chamber	$\pm 2 \text{ }^{\circ}\text{C} / \pm 3 \% \text{ RV}$
Ambient temperature	$\pm 1 \text{ }^{\circ}\text{C} (10-30)$
Time $\leq 1 \text{ hour}$	$\pm 0.2 \text{ s}$
Time $> 1 \text{ hour}$	$\pm 0.1 \% \text{ Reading}$
Torque	$\pm 5 \% \text{ Reading}$
Bending moment	$\pm 5 \% \text{ Reading}$
Standard weight	$\pm 5 \% \text{ Reading}$
Weighing $< 30 \text{ g}$	$\pm 0.1 \% \text{ Reading}$
Weighing $> 30 \text{ g}$	$\pm 2 \% \text{ Reading}$
Pressure (gas + air) general	$\pm 5 \% \text{ Reading}$
Barometer reading	$\pm 5 \text{ mbar}$
Pressure (water)	$\pm 5 \% \text{ Reading}$
Burst water pressure	$\pm 1 \% \text{ Reading}$
Gas tightness $0-100 \text{ cm}^3/\text{h}$	$\pm 5 \text{ cm}^3/\text{h}$
Gas tightness $> 100 \text{ cm}^3/\text{h}$	$\pm 5 \% \text{ Reading}$
Actual Flow rate (general)	$\pm 5 \% \text{ Reading}$

5 Appendices

Appendix 1 – Drawings	10
-----------------------------	----

Appendix 1 – Drawings

3 (pages)

6 End of report